



PRP3 - PMU

Project Director
(CDB - PRP1)
Road Development Authority

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS, PORTS & SHIPPING

ROAD DEVELOPMENT AUTHORITY

**CHINA DEVELOPMENT BANK FUNDED IMPROVEMENT
AND REHABILITATION OF
PRIORITY ROAD PROJECT 3 (PRP3), PHASE-1 (LOT 2)**

CIVIL WORK CONTRACT NO: RDA/RNIP/PRP3/PHASE-1 (LOT 2)/PACKAGE C12


Contract Component No.	Description
RDA/RNIP/PRP3/Phase1 (Lot 2)/Package C12	Ayagama - Egaloya Road (0.00 - 23.00 km)

CONTRACTOR
CHINA NATIONAL AERO - TECHNOLOGY INTERNATIONAL
ENGINEERING CORPORATION (CATIC - ENG)

VOLUME 4
The Drawings

JANUARY 2014

Handwritten signature



TYPICAL CROSS SECTION
NOT TO SCALE

PACKAGE C12

	ROAD NAME	CARRIAGWAY WIDTH	APPROXIMATE HARD SHOULDER WIDTH	APPROXIMATE EARTH SHOULDER WIDTH
C12	Ayagama - Egaloya Road (0.00 - 26.00km)	3.2 x 2	0.5 x 2	0.5 x 2

IS PROJECT - 3 (PHASE -1)

TYPICAL SECTIONS
ROAD PAVEMENT STRUCTURE


DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA
MINISTRY OF HIGHWAYS, PORTS & SHIPPING



DATE - NOV


PACKAGE C12

	ROAD NAME	CARRIAGWAY WIDTH	APPROXIMATE HARD SHOULDER WIDTH	APPROXIMATE EARTH SHOULDER WIDTH
C12	Ayagama - Egaloya Road (0.00 - 26.00km)	3.2 x 2	0.5 x 2	0.5 x 2




TYPICAL CROSS SECTION
NOT TO SCALE







TYPICAL CROSS SECTION



FOR DETAILS OF BENCHING AND FILL OVER MARSHY AREAS SEE DRAWING NO. ST009

TYPICAL CROSS SECTION






NOTES :-

1. ALL THE DIMENSIONS ARE IN mm UNLESS OTHERWISE STATED.
2. ABUTMENT BASE AND CONCRETE LINING SHALL BE STEPPED IF NECESSARY AS APPROVED BY THE ENGINEER.

t	
INLET	OUTLET
0	75

HALF SECTIONAL ELEVATION





ABUTMENT & HEADWALL LAYOUT - TYPE A

ABUTMENT & HEADWALL LAYOUT - TYPE B

TYPICAL DECK CULVERT ABUTMENT

PLAN




SLAB CULVERT WITH TYPE A HEADWALL


SLAB CULVERT WITH TYPE B HEADWALL

ELEVATION






HALF ELEVATION




ELEVATION

NOTES :


1. THIS DRAWING PROVIDES A GUIDANCE ONLY. EXACT DETAILS TO SUIT SITE CONDITIONS, SHALL BE DECIDED BY THE ENGINEER AT CONSTRUCTION STAGE.
2. BOX OPENING SIZE (NB & NO) MUST BE GREATER THAN OR EQUAL TO THE MINIMUM REQUIRED OPENING SIZE.
3. EXACT WALL THICKNESS (ts, tw, td and ti) AND R/F MUST BE DECIDED TO SUIT THE SITE CONDITION AND LOADING.
4. CONCRETE GRADE SHALL BE GR. 25(20).




DETAIL OF HEADWALL



PLAN





TYPICAL WINGWALL SECTIONS



TWIN BOX TYPE


SINGLE BOX TYPE




HALF SECTIONAL ELEVATION

NOTES :-

1. ALL THE DIMENSIONS ARE IN mm UNLESS OTHERWISE STATED.
2. TYPE OF HEAD WALL SHALL BE DECIDED BY THE ENGINEER TO SUIT THE SITE CONDITIONS.
3. PIPES SHALL BE LAID TO AGRADIENT OF 1 IN 200.
4. COLLARS TO BE USED IN CASE OF PIPES WITHOUT TONGUE AND GROOVE.
5. SLOPE OF EMBANKMENT FILL TO BE 1:1.5 OR AS DIRECTED AT SITE BY THE ENGINEER.
6. PRE CAST CONCRETE GUARD STONES SHALL BE FIXED AT 1500 C/C OR AS DIRECTED BY THE ENGINEER.
7. TYPE OF EMBANKMENT PROTECTION TO BE AS DIRECTED BY THE ENGINEER.




ABUTMENT & HEADWALL LAYOUT - TYPE A




ABUTMENT & HEADWALL LAYOUT - TYPE B

t	
INLET	OUTLET
0	75



SINGLE PIPE CULVERT WITH TYPE A HEADWALL




TWIN PIPE CULVERT WITH TYPE B HEADWALL

ELEVATION




NOTES :


- 1. THIS DRAWING PROVIDES A GUIDANCE ONLY. SITE DETAILS TO SUIT SITE CONDITIONS SHALL BE DECIDED BY THE ENGINEER AT CONSTRUCTION STAGE.
- 2. ALL DIMENSIONS ARE IN mm.




SECTION



SECTION




FOR TYPE -2




PLAN

TYPE 1- PIPE CULVERT



PLAN


TYPE 2- BOX CULVERT




FOR TYPE -1

TYPICAL R/F ARRANGEMENT FOR CULVERT INLETS






EARTH DRAIN



BUILT UP DRAIN WITH COVER











BUILT UP DRAIN

PRIORITY ROADS PROJECT - 3 (PHASE -1)

SMALL DRAINAGE STRUCTURES

DEMOCRATIC SOCIALIST REPUBLIC OF SRI LANKA

ROAD DEVELOPMENT
BATTARAMULLA



NOTE:


- THE DETAILS OF DRAINS OF ALL TYPES ARE AS DETERMINED AND TO SUIT SITE CONDITIONS.
- TOP LEVEL OF DRAIN SECTION IS TO BE DETERMINED WITH RESPECT TO ROAD FINISHED LEVEL.
- DRAIN TYPE (VI) IS TO BE ADOPTED IN REPAIRS OF EXISTING SECTIONS OF RANDOM RUBBLE MASONRY DRAINS. HOWEVER, IT COULD BE USED IN NEW SECTIONS SPECIALLY WHERE EXISTING OR MASONRY DRAINS HAVE TO BE EXTENDED.
- SUBSOIL DRAIN TYPE WILL BE LAID ACROSS THE SHOULDERS. THESE DRAINS SHOULD NOT BE LAID UNDER CARPAGESWAY.

m







DETAILS OF COVER SLABS (SEE TABLE 2)
SCALE 1:10



DETAILS OF 0.9M LONG PRE CAST CONCRETE KERB SECTIONS
SCALE 1:20



SECTIONAL ELEVATION OF KERB INLET
SCALE 1:10



DETAILS OF KERB INLET
SCALE 1:20






TABLE 2 DETAILS OF COVER SLABS

DRAIN TYPE	Slab	Length L	Width W	R/F (110)	Distri- bution	R/F Reinforcement				
						Distri- bution	Main	Distri- bution	Main	Distri- bution
I	1	1300	600	125	150	5 Nos.	10 Nos.	5 Nos.	10 Nos.	5 Nos.
	2	600	600	125	150	5 Nos.	10 Nos.	5 Nos.	10 Nos.	5 Nos.
	3	600	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.
II	1	800	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.
	2	600	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.
	3	500	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.
III	1	600	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.
	2	600	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.
	3	600	600	75	100	5 Nos.	6 Nos.	5 Nos.	7 Nos.	5 Nos.


PLAN OF THE WALKWAY & THE KERB INLET
SCALE 1:40





PART SECTIONAL ELEVATION ON X-X
SCALE 1:40






SECTIONAL ELEVATION ON Y-Y
SCALE 1:40



NOTE:
(i) PLACEMENT OF RESPECTIVE COVER SLABS FOR PEDESTRIAN & VEHICULAR ACCESS TO BE DECIDED AT SITE.
(ii) KERB INLETS SHOULD BE SPACED AT 1M INTERVALS.
(iii) ALL DIMENSIONS ARE IN MILLIMETERS UNLESS OTHERWISE SPECIFIED.




NOTE -
1. GRADE 20(20) CONCRETE TO BE USED IN CASTING KERBS.
2. MAXIMUM CASTING LENGTH 900mm.
3. ALL DIMENSIONS ARE IN MILLIMETERS.




m




STANDARD PRECAST EDGE USING KERB TYPE E1
SCALE - 1:5



STANDARD FOOTWALK/MEDIAN EDGE USING
KERB TYPE K2
SCALE - 1:10



STANDARD FOOTWALK / MEDIAN EDGE USING KERB TYPE K1
SCALE - 1:10



NOTE -
1. KERBS TO BE PAINTED IN BLACK & WHITE ALTERNATIVELY, PREFERABLY STARTING WITH WHITE & ENDING WITH WHITE.
2. ALL DIMENSIONS ARE IN MILLIMETERS.

THICKNESS AND THE LAYER TYPES
DEPEND ON THE FOOTWALKS/
CENTRE MEDIAN TYPE


THICKNESS & THE LAYER TYPES
DEPEND ON THE FOOTWALKS/
CENTRE MEDIAN TYPE

THICKNESS OF EACH LAYER
DEPENDS ON THE PAVEMENT
DESIGN.





u



m





- NOTE
- 1. GRADE 15 (20) CONCRETE TO BE USED IN CASTING THE GUARD STONE.
 - 2. GUARD STONE TO BE PLANTED ON FIRM GROUND AS DIRECTED BY THE ENGINEER.
 - 3. BOTTOM 100mm OF THE GUARD STONE TO BE PAINTED IN BLACK AND REMAINING TOP SECTION IN WHITE.
 - 4. ALL DIMENSIONS ARE IN MILLIMETRES.



NOTE


1. ALL CEMENT CONCRETE TO BE OF GRADE 20/20.
2. CLEAR COVER TO REINFORCEMENT TO BE 20mm.
3. TWO COATS OF ANTICORROSIIVE PAINT TO BE APPLIED TO THE EXPOSED AREA OF THE DOWEL.
4. ALL DIMENSIONS ARE IN MILLIMETERS.

SCHEDULE OF REINFORCEMENT									
LOCATION	MARK	DIA (mm)	NO. OF TYPE	CUT LENGTH (mm)	WEIGHT (kg)	BENDING	REMARKS		
COVER SLAB TYPE 1	a	10	5	860	2.65	50	560		
	b	10	4	560	1.38	50	560		
COVER SLAB TYPE 2	c	10	5	860	2.65	50	560		
	d	10	4	560	1.38	50	560		




CROSS SECTION A-A

SCALE - 1:5



SECTION THROUGH MOULD


SCALE - 1:5



NOTE -
 1. FIGURES 2,3,4,5,6 & 7 TO BE LATTEALLY REVERSED AND RIVETED TO PLATE SO THAT THE CASTS GIVE THEIR IMPRESSION.
 2. FIGURES TO BE PAINTED BLACK ON KILOMETRE STONE.
 3. FIGURES ON ROUTE NUMBERS SHOULD BE 2/3 FULL SIZE AND SHAPE OF FIGURES SHOWN ABOVE.
 4. 225mm x 225mm x 21mm RECESS TO BE LEFT FOR ROUTE NUMBERS ON FACE OF STONE.
 5. ALL DIMENSIONS ARE IN MILLIMETERS.


PLAN

SCALE - 1:5




ELEVATION

SCALE - 1:5




FRONT ELEVATION

SCALE - 1:10




6



SITING DETAILS OF WARNING SIGNS

TRAVEL SPEED km/h	CLEAR VISIBILITY DISTANCE (m)	DISTANCE FROM SIGN TO HAZARD (m)
80	75	160
60	60	100
50	60	60
40	60	45
30	60	45

NOTES:-
1. THE RETRO-REFLECTIVE SIGN SHALL BE DIAMOND TYPE.
2. ALL DIMENSION ARE IN mm. UNLESS OTHERWISE STATED.



REAR SIDE

REAR SIDE

